

University Engineering Department

Chandra Shekhar Azad University of Agriculture & Technology, Kanpur

No. CSAE- 106 /2026-27

Dated: 22/05/2026

QUOTATION NOTICE

Sealed quotations are invited by registered/speed post or by Courier for the following work by 29.05.2026 before 2:00 PM. Quotation by **ORDINARY POST** or **BY HAND** will not be accepted. Blank quotation form can be taken from the Officer In-charge, University Engineering department on any working day in office hours from 22.05.2026 Quotations will be opened on 29.05.2026 at 3:00 PM in presence of those quotationers who may like to be remain at that time.


University reserves the right to reject any or all the quotations without assigning any reason.

Name of work: Renovation of Room of Dr. Somveer Asso. Prof. in Plant breeding at CSA University Campus Kanpur.

S.I. No	Description of Item	QTY	UNIT	Rate as	Amount
1.	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	79.00	Sqm		
2.	Providing and applying white cement based putty of average thickness 1 mm. of approved brand and manufacturer. over the plastered wall surface to prepare the surface even and smooth complete	80.00	Sqm		
3.	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade. New work (Two or more coats applied @ 1.43 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	80.00	Sqm		
4.	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturer's specifications Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.75 ltr/10 sqm of approved brand and manufacture	11.00	Sqm		
5.	Providing and fixing angle iron frames for doors, windows and ventilators of mild steel Angle sections of size 35*35*5 mm. joints mitred and welded by angle iron 35x35x5 mm pr 35x 5 mm flat pieces to the existing I-iron frame or to the wall with dash fastener. including fixing of necessary butt hinges and screws and applying a priming coat of approved steel primer. all complete as per the direction of Engineer-In-charge.	11.00	kg		
6.	Renewing glass panes and refixing existing wooden fillets: Float glass panes of nominal thickness 4 mm (weight not less than 10kg/sqm)	6.00	Sqm		
7.	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 550x400 mm with a pair of 15 mm C.P. brass pillar taps	1	no		
8.	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. 25 mm nominal dia Pipes	2.00	Mtr		
9.	S.I. of 1.75 mm thick PVC Matt of Approved quality & design Shape color as Direction of EIC	23.50	Sq m		
				Total Rs	
				Add GST 18%	
				Add Labour Cess 1 %	
				Grand Total	
				Say	

CONDITIONS OF QUATATIONS:

1. The firms are requested to mention their GST number on their Pads it is compulsory to write the GST number on the Quotation.
2. Rate shall be inclusive GST & other all taxes and free delivery of University Campus.
3. Work shall be resumed within 05 days of the place in order and entire work to be complete within month.
4. In case of delay of work penalty up to 10% quoted cost may be imposed.
5. Quantities are liable to wide variations on either side even items may be all together omitted be compensation will be pai this account.
6. Work to be done strictly as per drawing and specifications and direction of the University Engineer.
7. Copy to Notice Board.
8. In charge A.K.M.U., C.S.A.U. of Ag & Tech Kanpur uploads for Univ. website.


(Naushad Khan)
Officer In Charge